


25-04-2018

CLINIC ROOF
MATERIAL REQUIRED

1	STEEL BARS $\frac{1}{2} \times 24 \times 95.00$	=	2,280.00
2	STEEL BARS $R8 \times 30 \times 35.00$	=	1,050.00
3	QUARR DUST OR R/SAND $1 \text{ load} \times 700.00$	=	700.00
4	BUILDING SAND $2 \text{ loads} \times 500.00$	=	1,000.00
5	BLOCKS OR BRICKS $1,000 \times 1.00$	=	1,000.00
6	SOFT WIRE $30 \text{ kg} \times 30.00$	=	900.00
7	CEMENT 40×75.00	=	3,000.00
8	TIMBER $150 \times 50 \times 5.0 \times 95 \times 105.00$	=	9,975.00
9	TIMBER $100 \times 50 \times 5.0 \times 20 \times 85.00$	=	1,700.00
10	TIMBER $75 \times 50 \times 5.0 \times 70 \times 80.00$	=	5,600.00
11	TIMBER FASCIA BOARD 30×105.00	=	3,150.00
12	WIRE NAILS $6" \times 50 \text{ kg} \times 25.00$	=	1,250.00
13	WIRE NAILS $4" \times 30 \text{ kg} \times 25.00$	=	750.00
14	WIRE NAILS $3" \times 10 \text{ kg} \times 25.00$	=	250.00
15	WIRE NAILS $2" \times 4 \text{ kg} \times 25.00$	=	100.00
16	WOOD PRESERVATIVE $20 \times 5 \text{ Ltrs} \times 35.00$	=	700.00
17	ROOF SHEETS $74 \times 4.0 \times 170.00$	=	12,580.00
18	RIDGES $2.0 \times 30 \times 80.00$	=	2,400.00
19	VALLEYS $2.0 \times 6 \times 80.00$	=	480.00
20	ROOFING NAILS $15 \text{ Pcs} \times 45.00$	=	675.00
21	DIESEL $50 \text{ Ltrs} \times 11.00$	=	550.00
22	ROLLER BRUSH 6×35.00	=	210.00
23	PAINT BRUSH $4" \times 4 \times 25.00$	=	100.00
			<hr/>
			50,400.00

TRANSPORT NOT INCLUDED.

PREPARED BY
DIAMOND MUSONDA



25-04-2018