

YMCA CAMP PEGGY LAKE PAVILIONS FOR ARCHERY RANGE AND BB GUN RANGE

Specifications:

16' x 24' x 8' Pole Barn **\$9,500**

6" x 6" Ground contact treated timbers for poles set in concrete, approx. 3 feet in ground

Ribbons: 2" x 12"/10" treated lumber

Roof: 2" x 4" construction, A frame trusses, overhang on all sides, hurricane fasteners.

Gable ends: Finished with 7/16", 8" grooved on center, pre-primed lp smart siding

Roof top: 7/16" OSB, synthetic underlayment, black architect asphalt shingles

Trim finish: 1 x 4 x 6" lp smart trim

Site prep: **\$2,500**

Tree and brush clearing, gravel pad for pole barn, hole digging and concrete for poles

These pole barns will establish a covered shooting area for the BB Gun Range and the Archery Range.

These areas are established but with the covered area additions, areas will be upgraded with additional tree and brush clearing and graveled shooting area.

Labor: **\$2,000**

Hire a contractor to plan and oversee construction.

Plan would be to have site work for structure to be completed and utilize volunteers under the direction of contractor to complete the building of the pole barns

Equipment Rental: **\$1,000**

Rental of bob cat/mini dozer to clear and prepare building site as well as the shooting lanes and target areas.

Total estimated cost for site prep and construction of 2 pole barns: **\$30,000**

As project is further developed, the YMCA expects to secure cash and in-kind donations along with funds in capital reserves to help with this and other capital projects for YMCA Camp Peggy Lake. Volunteer labor to assist with the site work and build will also help fund the project.