

With 4 toilet, wash basin for girls and 6 urinals ,2 toilets and wash basin for boys

Sl no	Details	No	L	B	D	Area
1	Earth work excavation in all soils Around walls	2	30.00	2.50	3.50	525.00
		2	12.00	2.50	3.50	210.00
	Septic tank	1	6.00	4.00	8.00	192.00
	Dispersion trench	1	8.00	4.00	8.00	256.00
						1183.00
2	Pcc 1:5:10 for foundation and flooring Around walls	2	30.00	2.00	0.33	39.60
		2	12.00	2.52	0.33	19.96
	Septic tank	1	6.00	4.00	0.33	7.92
	Flooring	1	30.00	12.00	0.33	118.80
						186.28
3	Size stone masonry in cm 1:6 Around walls	2	30.00	0.45	3.50	94.50
		2	12.00	2.50	3.50	210.00
						304.50
4	Brickwork in cm 1:5, 230mm thick Around walls	2	30.00	0.75	9.00	405.00
		3	12.00	0.75	9.00	243.00
	Septic tank	2	10.00	0.75	12.00	180.00
	Urinal area	1	15.00	0.75	1.00	11.25
	Deduction for door	-2	3.00	0.75	7.00	-31.50
						807.75
5	Brick partition wall in cm 1:4. 4.5" thk. Toilet partition wall	5	4.00		7.00	140.00
	Short wall	6	3.50		7.00	147.00
	Deduction	8	2.50		7.00	140.00
						427.00
6	Plastering in cm 1:5 , 12mm thick Around walls	4	30.00		9.00	1080.00
		6	12.00		9.00	648.00
	Septic tank	2	10.00		12.00	240.00
	Urinal area	1	15.00		2.00	30.00
	Deduction for door	-4	3.00		7.00	-84.00
	Toilet partition wall	10	4.00		7.00	280.00
	Short wall	6	3.50		7.00	147.00
	Deduction	6	2.50		7.00	105.00
	Septic tank ceiling	1	6.00		4.00	24.00
						2470.00
7	Supplying and laying of wall and floor tiles Around walls	2	30.00		5.00	300.00
		4	12.00		5.00	240.00
	Urinal area	1	15.00		2.00	30.00
	Deduction for door	-2	3.00		5.00	-30.00

	Toilet partition wall	10	4.00		5.00	200.00
	Short wall	6	3.50		5.00	105.00
	Deduction	6	2.50		5.00	75.00
	Flooring	1	30.00		12.00	360.00
						1280.00
8	Supply and fixing of cudappah slab for urinal partition					
		5	1.75		4.00	35.00
9	Supply and fixing of indian type closet including all necessary fittings	6				12.00
10	Supply and fixing of urinals with necessary fittings	6				6.00
11	Supply and fixing of wash basins with all necessary fittings	2				2.00
12	Rcc 1:2:4 for roof slab including shuttering and reinforcement					
	Septic rank	1	6.00	4.00	0.38	9.12
	Manhole covers	4	2.00	2.00	0.05	0.80
						9.92
13	Supplying and fixing of RCC Jally work for ventilation					
		12				12.00
14	Supply and fixing of PVC doors for toilets	6				6.00
15	Supply and fixing of steel door for main entrance	2				2.00
16	Water supply and sanitary pipes					
17	Electical work					
18	White washing two coats					
	Around walls	4	30.00		4.00	480.00
		3	12.00		4.00	144.00
	Deduction for door	-4	3.00		4.00	-48.00
	Toilet partition wall	10	4.00		4.00	160.00
	Short wall	6	3.50		4.00	84.00
						820.00
20	Laying of soling stone for dispersion trench	1	8.00	4.00	8.00	256.00
	Galve alume sheet roofing	1	30	14		420.00