B.SRINIVASAN.B.E.,
SRI KRISHNA BUILDERS
TRICHY - 620 017
PHONE 9443125509

RR. COMPLEX, 6F ALLITHURAI ROAD , PUTHUR, TRICHY.17

ABSTRACT ESTIMATE

THIS ESTIMATE FOR PRO.CONSTRUCTION OF HYDRO THERAPY UNIT FOR ATHMA SPECIAL SCHOOL , (ATHMA EDUCATION &RESEARCH FOUNDATION)
S.FO: 817, ENAMKULATHUR, TRICHIRAPPALLI. 620009

1	Earth work excavation for foundation up to a depth of 6'0" from ground level	325.00	Cu.M.	300.00	Cu.M.	97,500.00
2	Sand filling in foundation trench 1' clean river Sand.	87.00	Cu.M.	650.00	Cu.M.	56,550.00
3	Plain cement concrete mix 1:4:8 using hand broken granite metal 1'0" thick.	53.00	Cu.M.	3,200.00	Cu.M.	169,600.00
4	Reinforced cement concrete works with M20 mix using 20mm machine crushed baby jelly.	56.00	Cu.M.	17,000.00	Cu.M.	952,000.00
5	Brick work for superstructre with c.m 1:5 using chamber bricks for 9" thick walls.	23.00	Cu.M.	5,200.00	Cu.M.	119,600.00
6	Quality ceramic Swimming water proof tile flooring with quality adhessive chemicals	324.00	Sq.M	2,000.00	Sq.M.	648,000.00
7	Supplying and installstion of ss handrails allround and ladder with complete safety measurements					75,000.00
8	Supplying and installstion with a run of pvc conduit pipe wiring with 1/18 and 3/20 lighting purpose finolex wiring with modular switches and sockets			L.S.		50,000.00
9	Provision for unforseen charges etc., complete			L.S.		1,750.00
				TOTAL Rs.		**2,170,000.00**
				TOTAL Rs.		**21,70,000.00**

(RUPEES TWENTY ONE LAKHS AND SEVENTY THOUSAND ONLY)

DATE :
PLACE : TRICHY.

CONSULTING ENGINEER

B.SRINIVASAN, B.E., M.A.,(Yoga)
CONSULTING CIVIL ENGINEER & LICENSED BUILDING SURVEYOR
R.R. COMPLEX
6/F, VAYALOORE ROAD
PUTHUR, TRICHY - 17
CELL : 9443125509